

HDR
 Firm Registration No. F-754
 17111 Preston Road, Suite 300
 Dallas, Texas 75248-1229
 972.960.4400




Gibbons Creek Environmental
 Redevelopment Group, LLC

Construction Drawings For

Gibbons Creek Electric Station

Scrubber Sludge Pond Ash Ponds




VICINITY MAP
 NOT TO SCALE

Project No.
 10290148

Anderson, Texas
 May 2021

INDEX OF DRAWINGS

GENERAL	
00G-01	COVER SHEET
00G-02	ABBREVIATIONS AND GENERAL NOTES
CIVIL	
00C-01	SITE LAYOUT
00C-02	DEMOLITION PLAN
00C-03	SCRUBBER SLUDGE POND PROPOSED FINAL
00C-04	SCRUBBER SLUDGE POND CROSS SECTIONS
00C-05	ASH PONDS PROPOSED FINAL
00C-06	ASH PONDS CROSS SECTIONS
00C-07	DETAILS



[Signature]
 6-7-21

STANDARD ABBREVIATIONS

&	AND	NTS	NOT TO SCALE
APPROX	APPROXIMATELY	NTYS	NORTH THICKENER YARD SUMP
@	AT	OC	ON CENTER
AVG	AVERAGE	OZ	OUNCE
APS	ASH PONDS	%	PERCENT
BOE	BOTTOM OF EXCAVATION	PLCP	PERFORATED LEACHATE COLLECTION PIPE
BOL	BOTTOM OF LINER	PERF	PERFORATED
X	BY	PGL	PROFILE GRADE LINE
CL	CENTERLINE	PC	POINT OF CURVATURE
CMP	CORRUGATED METAL PIPE	PI	POINT OF INTERSECTION
CO	CLEAN OUT	PVI	POINT OF VERTICAL INTERSECTION
CY	CUBIC YARD	PT	POINT OF TANGENT
DIA	DIAMETER	PZ	PIEZOMETER
DET	DETAIL	Q	FLOW
DWG	DRAWING	QTY	QUANTITY
E	EAST	R	RADIUS
ELEV	ELEVATION	RCP	REINFORCED CONCRETE PIPE
EW	EACH WAY	REF	REFERENCE
EXIST	EXISTING	REQ	REQUIRED
EXC	EXCAVATION	RD	ROAD
FGD	FLUE GAS DESULFICATION	SCH	SCHEDULE
FML	FLEXIBLE MEMBRANE LINER	SDL	SAND DRAINAGE LAYER
FT	FEET	SEC	SECTION
GAL	GALLON	SFL	SITE F LANDFILL
GCSES	GIBBONS CREEK STEAM ELECTRIC STATION	SHT	SHEET
GCERG	GIBBONS CREEK ENVIRONMENTAL REDEVELOPMENT GROUP	S	SOUTH
GND	GROUND	SDR	STANDARD DIMENSION RATIO
GDL	GRAVEL DRAINAGE LAYER	SLQCP	SOIL LINER QUALITY CONTROL PLAN
GNDL	GEONET DRAINAGE LAYER	SP	STEEL PIPE
HDPE	HIGH DENSITY POLYETHYLENE	SSP	SCRUBBER SLUDGE POND
HORIZ	HORIZONTAL	SQ	SQUARE
ID	INSIDE DIAMETER	SS	SIDE SLOPE
IN	INCHES	STA	STATION
IE	INVERT ELEVATION	STYS	SOUTH THICKENER YARD SUMP
LCRS	LEACHATE COLLECTION AND REMOVAL SYSTEM	T.A.S.	TERMINAL ANCHOR SECTION
LCS	LEACHATE COLLECTION SYSTEM	TL	TANGENT LENGTH
LCP	LEACHATE COLLECTION PIPE	TOC	TOP OF COVER
LCPR	LEACHATE COLLECTION PIPE RISER	TOFC	TOP OF FINAL COVER
LF	LINEAR FEET	TOL	TOP OF LINER
LB	POUND	TOS	TOE OF SLOPE
MH	MANHOLE	TS	TOP SLOPE
MAX	MAXIMUM	TEMP	TEMPORARY
MIL	.001 INCHES	TYP	TYPICAL
MIN	MINIMUM	UNO	UNLESS NOTED OTHERWISE
MW	MONITOR WELL	VERT	VERTICAL
MSL	MEAN SEA LEVEL	W	WEST
N	NORTH	W/	WITH
NIC	NOT IN CONTRACT	WW	WETWELL
NO	NUMBER	YD	YARD


GENERAL NOTES

- ALL WORK UNDER THIS CONTRACT SHALL BE PERFORMED IN ACCORDANCE WITH THE PLANS AND PROJECT SPECIFICATIONS. IN THE EVENT OF A DISCREPANCY BETWEEN THE PLANS AND THE PROJECT SPECIFICATIONS, THE SPECIFICATIONS SHALL GOVERN.
- COORDINATE SYSTEM IS BASED ON LOCAL SURVEY. THE BENCHMARKS TO BE USED FOR CONSTRUCTION ARE LOCATED AS SHOWN ON DRAWING NO. 00G-01. EXISTING CONTOURS ARE BASED ON TOPOGRAPHICAL SURVEY PERFORMED FEBRUARY 12-20, 2019 BY LACY SURVEYING. CURRENT GROUND ELEVATIONS MAY VARY FROM THOSE SHOWN DUE TO SITE WORK THAT HAS BEEN PERFORMED SINCE THE SURVEY WAS PERFORMED.
- THE CONTRACTOR SHALL VERIFY EXISTING CONTOURS PRIOR TO THE START OF WORK.
- THERE SHALL NOT BE ANY ADDITIONAL PAYMENT OR EXTENSION OF CONTRACT TIME FOR WORKING WITH SATURATED SOILS OR HANDLING WATER SEEPAGE DUE TO RAINFALL, RUNOFF AND INFILTRATION.
- THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT EXISTING ROADS, BENCHMARKS AND EXISTING GROUNDWATER MONITOR WELLS DURING THE CONSTRUCTION PERIOD. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PROTECT THE GROUNDWATER MONITOR WELLS, BENCHMARKS AND EXISTING ROADS.
- THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES HAVE NOT BEEN ESTABLISHED BY THE OWNER OR ENGINEER. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING PROPER SAFE WORKING DISTANCE FROM ALL UTILITY EASEMENTS OR LINES.
- EXCAVATION BY "BLASTING" IS NOT PERMITTED ON THIS PROJECT.
- FINISHED GROUND ELEVATIONS SHALL MATCH EXISTING GROUND ELEVATIONS EXCEPT AS SHOWN ON THE PLANS. ALL EXCESS SOIL FROM THE EXCAVATION AND GRADING SHALL BE PLACED IN DESIGNATED STOCKPILE LOCATIONS AS APPROVED BY THE OWNER. IF WASTE IS ENCOUNTERED DURING EXCAVATION, THE OWNER SHALL BE NOTIFIED AND THE WASTE REMOVED AND PLACED IN AREAS DESIGNATED AS APPROVED BY THE OWNER. TRANSPORT OF SOIL TO FILL AREAS SHALL BE CONDUCTED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER.
- THE CONTRACTOR SHALL CONSTRUCT, AND UPON COMPLETION OF THE PROJECT, REMOVE TEMPORARY CONSTRUCTION ACCESS ROADS. SUCH ROADS SHALL BE LOCATED AS APPROVED BY THE OWNER. DRAINAGE PATTERNS AT THE SITE SHALL NOT BE ALTERED BY ROAD CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION AND MAINTENANCE OF TEMPORARY DRAINAGE STRUCTURES, INCLUDING CULVERTS, AT NO ADDITIONAL COST TO THE OWNER.
- THE CONTRACTOR SHALL INSTALL, MAINTAIN, AND UPON COMPLETION OF THE PROJECT, REMOVE TEMPORARY EROSION AND SEDIMENT CONTROLS AS APPROVED BY GCERG AND IN ACCORDANCE WITH THE SITE SWPPP AND PURSUANT TO TPDES REQUIREMENTS. SUCH CONTROLS SHALL BE PLACED AT THE LIMITS OF DISTURBED AREAS AND AT INTERMEDIATE LOCATIONS WHERE CONCENTRATED FLOW IS LIKELY.
- TEMPORARY CONSTRUCTION SLOPES SHALL NOT BE GREATER THAN 2H:1V. STEEPER SLOPES WILL ONLY BE ALLOWED IF THE CONTRACTOR PROVIDES A GEOTECHNICAL ENGINEERING REPORT SPECIFYING MAXIMUM SLOPES AND THE DURATION FOR WHICH SUCH SLOPES SHALL REMAIN IN PLACE.
- THE CONTRACTOR SHALL REMOVE ALL VEGETATION WITHIN THE CONSTRUCTION LIMITS AS REQUIRED TO CONSTRUCT THE PROJECT. ALL VEGETATION SHALL BE REMOVED BY CONTRACTOR AT NO ADDITIONAL EXPENSE TO OWNER.
- THE CONTRACTOR SHALL OBTAIN AND CONDUCT WORK CONSISTENT WITH A TPDES PERMIT FOR CONSTRUCTION, REFER TO TECHNICAL SPECIFICATIONS. PREPARATION OF A SWPPP AND OBTAINING THE TPDES PERMIT ARE THE CONTRACTORS RESPONSIBILITY.
- THE CONTRACTOR SHALL IMMEDIATELY REPORT TO THE ENGINEER ANY ERROR OR DISCREPANCY FOUND ONCE THE CONTRACT DOCUMENT IS CAREFULLY REVIEWED AND ALL ASPECTS OF FIELD WORK HAVE BEEN VERIFIED. IN THE EVENT THE CONTRACTOR CONTINUES TO WORK ON AN ITEM WHERE AN ERROR EXISTS, IT SHALL BE DEEMED THAT THE CONTRACTOR BID AND INTENDED TO EXECUTE THE MORE STRINGENT OR HIGHER QUALITY REQUIREMENT WITHOUT AN INCREASE IN CONTRACT SUM OR TIME. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE TO CORRECT ANY FAILURE OF COMPANY PARTS TO COORDINATE OR FIT PROPERLY INTO FINAL POSITION, AS A RESULT OF CONTRACTOR FAILURE TO RAISE OR RESOLVE A DISCREPANCY.
- THE DRAWINGS AND SPECIFICATIONS SHOULD AGREE WITH EACH OTHER, AND WORK CALLED FOR BY DRAWINGS AND NOT MENTIONED IN SPECIFICATION, OR VICE VERSA, SHALL BE FURNISHED BY BOTH. WHEN DISCREPANCIES EXIST BETWEEN SCALE AND DIMENSIONS, THE DIMENSIONED FIGURE SHALL BE USED.
- CONTRACTOR AND EACH SUBCONTRACTOR SHALL VERIFY ALL GRADES, LINES, LEVELS, AND DIMENSIONS AS INDICATED ON DRAWINGS, AND HE SHALL REPORT ERRORS TO THE ENGINEER BEFORE COMMENCING WORK. THE CONTRACTOR SHALL ESTABLISH BENCHMARKS IN AT LEAST TWO WIDELY SEPARATED PLACES, AND AS WORK PROGRESSES THE CONTRACTOR WILL MAINTAIN ADEQUATE HORIZONTAL AND VERTICAL CONTROL.
- CONTRACTOR SHALL PROVIDE EROSION CONTROL BY SEEDING FOR ALL AREAS DISTURBED BY CONTRACTOR DURING THE CONSTRUCTION OF THIS PROJECT. THE CONTRACTOR SHALL NOT DISTURB ANY AREA WITHOUT THE APPROVAL OF THE ENGINEER. EROSION CONTROL BY SEEDING SHALL CONFORM TO STANDARD SPECIFICATION 02930.
- CONTRACTOR SHALL INSTALL EROSION AND SEDIMENT CONTROLS AS PER SPECIFICATIONS DURING CONSTRUCTION. SUCH CONTROLS SHALL BE PLACED AT LIMITS OF DISTURBED AREAS AND AT INTERMEDIATE LOCATIONS WHERE CONCENTRATED FLOW IS LIKELY.
- STORMWATER THAT HAS COME INTO CONTACT WITH THE ASH WITHIN THE EXCAVATED POND IS TO BE CONSIDERED CONTACT STORMWATER. CONTRACTOR WILL CONTROL THE WATER ON SITE IN COMPLIANCE WITH THE TPDES PERMIT AND THE PROJECT WATER MANAGEMENT PLAN, THE LATEST EDITION.
- THE CONTRACTOR IS REQUIRED TO ADHERE TO THE PROJECT SWPPP AND COORDINATE ANY CHANGES OR ADDITIONS WITH GCERG FOR APPROVAL.
- CCR MATERIAL EXCAVATED FROM THE APS AND SSP SHALL BE HAULED TO THE SFL FOR DISPOSAL. CCR MATERIAL SHALL BE SUFFICIENTLY DRIED TO PASS A PAINT FILTER TEST PRIOR TO PLACEMENT AT THE SFL.
- NO CCR MATERIAL WILL BE PERMITTED TO BE SPILLED FROM THE HAUL TRUCKS. ANY CCR MATERIAL SPILLED ON THE HAUL ROUTE MUST IMMEDIATELY BE CONTAINED AND REMOVED. THE CONTRACTOR SHALL FOLLOW CHARAH'S CCR SPILL RESPONSE PLAN AND COORDINATE ANY SPILL WITH CHARAH/GCERG AS REQUIRED.




SYMBOLS

SECTION DETAIL INDICATORS


DRAWING ON WHICH SECTION IS CUT:




DRAWING ON WHICH SECTION APPEARS:




CURVE WITH HORIZONTAL CONTROL:





VERTICAL CONTROL DESIGNATION



DRAWING ON WHICH DETAIL IS INDICATED:




DRAWING ON WHICH DETAIL APPEARS:



ISSUE	DATE	DESCRIPTION

PROJECT MANAGER D. VOGT, P.E.	
PROJECT NUMBER	10290148




Gibbons Creek Environmental Redevelopment Group, LLC
GIBBONS CREEK ELECTRIC STATION
 Anderson, Texas

ABBREVIATIONS AND GENERAL NOTES


0 1" 2" FILENAME 00G-02.dwg SCALE

SHEET 00G-02




Point Table				
Point #	Elevation	Northing	Easting	Description
1	264.41	10215059.23	3635496.52	HV1
2	267.13	10215059.22	3634773.42	HV2
3	277.72	10215596.80	3632301.37	HV3
4	285.94	10215834.35	3631214.93	HV4
5	282.00	10211270.16	3634674.60	HV5
6	285.67	10211333.35	3635637.42	HV6

BENCHMARKS SHOWN REFERENCE TEXAS STATE PLANE, CENTRAL ZONE NAD 83, US FOOT




ISSUE	DATE	DESCRIPTION

PROJECT MANAGER D. VOGT, P.E.	
PROJECT NUMBER	10290148




Gibbons Creek Environmental Redevelopment Group, LLC
GIBBONS CREEK ELECTRIC STATION
 Anderson, Texas



SITE LAYOUT


FILENAME | 00C-01.dwg
 SCALE |

SHEET
00C-01




- NOTES:
1. REMOVE ALL PIPEWORK IN SSP AND ASP A MINIMUM OF 50' BEYOND LIMITS OF POND. GROUT AND CAP REMAINING PIPE.
 2. LOCATIONS OF PIPE, CONDUIT AND STRUCTURES ARE APPROXIMATE AND BASED ON LIMITED AS-BUILT INFORMATION, FIELD OBSERVATIONS AND INTERVIEWS WITH STAFF. ACTUAL FIELD CONDITIONS MAY VARY.
 3. DRAINAGE PIPE UNDER BERM SEPARATING ASH POND "A" FROM ASH POND "B" MUST REMAIN UNTIL POND "A" IS DEWATERED AND EMPTY. DRAINAGE PIPE UNDER BERM SEPARATING ASH POND "B" FROM ASH POND "C" SHALL BE REMOVED AFTER DEWATERING OF ASH PONDS "B" AND "C" IS COMPLETE.

PROJECT MANAGER D. VOGT, P.E.




ISSUE	DATE	DESCRIPTION

PROJECT NUMBER	10290148
----------------	----------




Gibbons Creek Environmental Redevelopment Group, LLC
GIBBONS CREEK ELECTRIC STATION
 Anderson, Texas

DEMOLITION PLAN



FILENAME | 00C-02.dwg
 SCALE | 1"=200'

SHEET
00C-02



- LEGEND**
- EXISTING MINOR CONTOUR
 - - - 320 - - - EXISTING MAJOR CONTOUR
 - PROPOSED MINOR CONTOUR
 - 320 — PROPOSED MAJOR CONTOUR

- NOTES:**
1. CONTRACTOR SHALL DEWATER THE SSP IN ACCORDANCE WITH THE PROJECT WATER MANAGEMENT PLAN, LATEST REVISION AND AS DIRECTED BY CHARAH/GCERG.
 2. CONTRACTOR TO REMOVE ALL CCR MATERIAL FROM THE POND AND HAUL IT TO THE SFL FOR DISPOSAL.
 3. CCR MATERIAL SHALL BE REMOVED TO A VISUAL STANDARD AS DETERMINED BY THE PROJECT ENGINEER.
 4. CONTRACTOR TO DETERMINE AND INSTALL APPROPRIATE STORMWATER POLLUTION PREVENTION BMPs IN ACCORDANCE WITH THE STORM WATER POLLUTION PREVENTION PLAN.
 5. ANY STORMWATER THAT CONTACTS CCR MATERIAL IN THE SSP MUST BE TREATED AS CONTACT WATER AND CONVEYED PER THE PROJECT WATER MANAGEMENT PLAN AND DISCHARGED IN COMPLIANCE WITH THE TPDES PERMIT.
 6. GEOMEMBRANE MATERIAL SHALL BE SEGREGATED FROM THE CCR MATERIAL. GEOMEMBRANE MATERIAL TO BE STACKED AT SFL AT THE LOCATION INDICATED ON THE SITE LAYOUT FOR DISPOSAL.
 7. CONTRACTOR TO NOTIFY ENGINEER AND OWNER A MINIMUM OF 48 HOURS IN ADVANCE FOR CCR REMOVAL CERTIFICATION INSPECTION AND/OR CONSTRUCTION PROGRESS SURVEYS.
 8. PIPE, CONCRETE, AND OTHER CONSTRUCTION DEBRIS MUST BE HAULED OFFSITE AND DISPOSED IN AN AUTHORIZED MANNER.
 9. CONTRACTOR TO INSTALL VEGETATION UPON COMPLETION OF THE CERTIFICATION IAW TXDOT SPECIFICATION 164. CONTRACTOR SHALL CONTINUE TO WATER AND MAINTAIN AREA UNTIL VEGETATION ESTABLISHED.


CUT APPROXIMATELY 4,290 CY OF BERM. PROVIDE 4,470 SF OF ROCK RIPRAP (TXDOT STONE COMMON) DRY (12" TYP.) SEE DETAIL 2

INSTALL PERMANENT ROCK DAM PER TXDOT DETAIL EC(2)-16

ROCK RIPRAP (STONE COMMON) DRY (12" TYP.) SEE DETAIL 2


SCRUBBER SLUDGE POND

ASH PONDS




ISSUE	DATE	DESCRIPTION

PROJECT MANAGER D. VOGT, P.E.	
PROJECT NUMBER	10290148




Gibbons Creek Environmental Redevelopment Group, LLC
GIBBONS CREEK ELECTRIC STATION
 Anderson, Texas



FILENAME | 00C-03.dwg
 SCALE | 1"=100'


SHEET
00C-03

**SCRUBBER SLUDGE POND
 PROPOSED FINAL CONTOURS**




LEGEND
 - - - - - EXISTING GROUND SURFACE
 _____ PROPOSED GRADE


- NOTES:**
- CCR ELEVATION FROM LIDAR SURVEY TAKEN JAN. 01 2021 BY LACY SURVEYING OF ARP, TEXAS.
 - CONTRACTOR WILL REMOVE ALL CCR MATERIAL TO A VISUAL STANDARD AS DETERMINED BY PROJECT ENGINEER.
 - PROPOSED POND FLOOR ELEVATIONS ARE APPROXIMATE BASED ON THE NARRATIVE DESCRIPTION OF THE POND IN THE 2016 HISTORY OF CONSTRUCTION REPORT BY ERM.



SECTION A-A
 HORIZONTAL SCALE: 1" = 100'; VERTICAL SCALE: 1" = 20'




SECTION B-B
 HORIZONTAL SCALE: 1" = 100'; VERTICAL SCALE: 1" = 20'




ISSUE	DATE	DESCRIPTION

PROJECT MANAGER D. VOGT, P.E.	
PROJECT NUMBER	10290148





Gibbons Creek Environmental Redevelopment Group, LLC
GIBBONS CREEK ELECTRIC STATION
 Anderson, Texas



FILENAME | 00C-04.dwg
 SCALE | AS SHOWN

SCRUBBER SLUDGE POND CROSS SECTIONS




LEGEND

- EXISTING MINOR CONTOUR
- - - - 320 - - - - EXISTING MAJOR CONTOUR
- PROPOSED MINOR CONTOUR
- 320 — PROPOSED MAJOR CONTOUR


NOTES:

1. CONTRACTOR SHALL DEWATER THE APS IN ACCORDANCE WITH THE PROJECT WATER MANAGEMENT PLAN, LATEST REVISION AND AS DIRECTED BY CHARAH/GCERG.
2. CONTRACTOR TO REMOVE ALL CCR MATERIAL FROM THE POND AND HAUL IT TO THE SFL FOR DISPOSAL.
3. CCR MATERIAL SHALL BE REMOVED TO A VISUAL STANDARD AS DETERMINED BY THE PROJECT ENGINEER.
4. CONTRACTOR TO DETERMINE AND INSTALL APPROPRIATE STORMWATER POLLUTION PREVENTION BMPs IN ACCORDANCE WITH THE STORM WATER POLLUTION PREVENTION PLAN. ANY STORMWATER THAT CONTACTS CCR MATERIAL MUST BE TREATED AS CONTACT WATER AND CONVEYED PER THE PROJECT WATER MANAGEMENT PLAN AND DISCHARGED IN COMPLIANCE WITH THE TPDES PERMIT.
5. CONTRACTOR TO NOTIFY ENGINEER AND OWNER A MINIMUM OF 48 HOURS IN ADVANCE FOR CCR REMOVAL CERTIFICATION INSPECTION AND/OR CONSTRUCTION PROGRESS SURVEYS.
6. PIPE, CONCRETE, AND OTHER DEMOLITION DEBRIS MUST BE HAULED OFFSITE AND DISPOSED IN AN AUTHORIZED MANNER.
7. CONTRACTOR TO INSTALL VEGETATION UPON COMPLETION OF THE CERTIFICATION IAW TXDOT SPECIFICATION 164. CONTRACTOR SHALL CONTINUE TO WATER AND MAINTAIN AREA UNTIL VEGETATION ESTABLISHED.




ISSUE	DATE	DESCRIPTION

PROJECT MANAGER D. VOGT, P.E.	
PROJECT NUMBER	10290148





**Gibbons Creek Environmental
Redevelopment Group, LLC**
GIBBONS CREEK ELECTRIC STATION
Anderson, Texas






**ASH PONDS
PROPOSED FINAL CONTOURS**

FILENAME | 00C-05.dwg
SCALE | 1"=100'

SHEET
00C-05




- NOTES:
- CCR ELEVATION FROM LIDAR SURVEY TAKEN JAN. 01 2021 BY LACY SURVEYING OF ARP, TEXAS.
 - CONTRACTOR WILL REMOVE ALL CCR MATERIAL TO A VISUAL STANDARD AS DETERMINED BY PROJECT ENGINEER.
 - PROPOSED POND FLOOR ELEVATIONS ARE APPROXIMATE BASED ON THE 1979 "ENLARGED SITE PLAN SECTION NO. 10" DRAWING 11-C-204.




ISSUE	DATE	DESCRIPTION

PROJECT MANAGER	D. VOGT, P.E.
PROJECT NUMBER	10290148




Gibbons Creek Environmental Redevelopment Group, LLC
GIBBONS CREEK ELECTRIC STATION
Anderson, Texas




ASH PONDS CROSS SECTIONS

FILENAME | 00C-06.dwg
SCALE | AS SHOWN


SHEET
00C-06



ASH POND FLOW LINE
NOT TO SCALE



RIPRAP CHANNEL
NOT TO SCALE



RIPRAP CHANNEL
NOT TO SCALE

DISCLAIMER: It is expected that the user of this document will be responsible for the design and construction of any structure shown herein. The user should consult with the designer for any questions or for clarification of any detail shown herein.

FILES: RFD1, RFD2, RFD3, RFD4

GENERAL NOTES

- If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream of drainage structures, and in roadway ditches and channels to collect sediment.
- Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
- The rock filter dam dimensions shall be as indicated on the SW3P plans.
- Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
- Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
- Filter dams should be embedded a minimum of 4" into existing ground.
- The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
- Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
- Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4".
- Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
- The guidelines shown herein are suggestions only and may be modified by the Engineer.

PLAN SHEET LEGEND

- Type 1 Rock Filter Dam (RFD1)
- Type 2 Rock Filter Dam (RFD2)
- Type 3 Rock Filter Dam (RFD3)
- Type 4 Rock Filter Dam (RFD4)

ROCK FILTER DAM USAGE GUIDELINES

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT² of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 ft/sec or more). In which aggregate wash out may occur. Sandbags may be used on the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in stream flow and should be secured to the stream bed.


Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 may be used in ditches and smaller channels to form an erosion control dam.


Type 5: Provide rock filter dams as shown on plans.

Texas Department of Transportation
Design Division Standard
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES
ROCK FILTER DAMS
EC(2)-16


FILE# ec216	DATE 10/07	DESIGNER DM	INCH LS
TXDOT# JULY 2016	CONV SECT	JOB	ROADWAY
REVISED	DIST	COUNTY	SHEET NO.



ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	PROJECT MANAGER
			10290148	D. VOGT, P.E.



Gibbons Creek Environmental Redevelopment Group, LLC
GIBBONS CREEK ELECTRIC STATION
Anderson, Texas



FILENAME: 00C-07.dwg
SCALE: AS SHOWN

SHEET
00C-07

DETAILS